



# Tewksbury Water Distribution System

# Distribution System Background

- Construction on the Water Distribution System began in 1951
- By 1953 approximately 60 miles of Asbestos Cement (AC) water main was installed
- Wrought Iron was used for additional piping on minor roadways
- The Town began using Cast Iron (CI) in 1953
- The Town transitioned to Cement Lined Ductile Iron (CLDI) pipe in the early 1980s
- The Total Distribution System network includes:
  - 160 miles of water main
  - Three storage tanks totaling 7 Million Gallons
  - Approx. 10,000 water services

# Asbestos Cement (AC) Pipe



- AC pipe was the first water main pipe used in Tewksbury
- Between 1951 and 1953 approximately 60 miles of AC water main was installed
- The Life Expectancy of AC pipe is about 50-years, but installation conditions reduce the lifespan
- The joint between pipe sections are the weak point where we find most failures occur
- AC pipe experiences devastating failure without warning
- Currently there is 54.9 miles of AC pipe remaining in the system

# Wrought Iron (WI) Pipe



- Wrought Iron was used for additional piping on minor roadways most notably in South Tewksbury
- This pipe is uncoated or has minimal galvanized lining that deteriorates quickly over time
- The pipe forms tuberculation that reduce capacity and create water quality issues
- Many roads in South Tewksbury have 2-inch WI water mains that are close to 70 years old
- There is approximately 3.9 miles of WI pipe in the system

# Cast Iron (CI) Pipe



- Lined with cement to prevent tuberculation
- The Life Expectancy of CI pipe is 50-120 years
- Was superseded by Cement Lined Ductile Iron Pipe in the 1980s
- There is approximately 28.6 miles of CI pipe in the system

# Cement Lined Ductile Iron (CLDI) Pipe



- Lined with cement to prevent tuberculation
- The Life Expectancy of CLDI pipe is 60-130 years
- There is approximately 68.2 miles of CLDI pipe in the system
- This is the current pipe type that the Town installs
- There are significant supply chain issues with CLDI (approx. 40 weeks)

# Polyvinyl Chloride (PVC) C909 Pipe



- Life Expectancy of PVC Pipe is 100-150 years
- PVC Pipe material cost is approximately half that of CLDI
- Pipe availability has not been impacted as severely by supply chain issues
- Delivery times are 30-days or less
- The installation process is similar to CLDI pipe

# Life Expectancies of Pipe Materials


Pipe Material	100%	50%	10%
Asbestos Cement	50	75	100
Cast Iron	50	80	120
Ductile Iron	60	90	130
PVC	100	130	150

Source: Fisher, C. (2008, January/February). Choosing the Right Pipe. *Underground Infrastructure Management*, pp. 30-32

Actual life expectancy for Asbestos Cement and Cast Iron and can be highly variable depending on the quality and location of installation.




# Water Mapping Project



# Water System Pipe Material

PIPE MATERIAL	LENGTH (MILES)	PERCENTAGE
DI	68.21	42.6%
AC	54.87	34.3%
CI	28.55	17.8%
UNKNOWN	4.16	2.6%
WI	3.94	2.5%
STEEL	0.16	0.1%
PLASTIC	0.13	0.1%



# Water Main Breaks and Service Leaks

<b>Year</b>	<b>Service Leaks</b>	<b>Main Breaks</b>	<b>Total</b>
2018	14	48	<b>62</b>
2019	10	39	<b>49</b>
2020	15	32	<b>47</b>
2021	18	32	<b>50</b>
2022	4*	34*	<b>38</b>
<b>Total</b>	<b>61</b>	<b>185</b>	<b>246</b>
*Through October 2022			

# Completed/Ongoing Water Projects

Project Name	Year	Length (ft.)	Total Cost
Contract 802797 Shawsheen St., Crest Rd., Main St., Clark Rd.	2015	4,449	\$1,374,302
PW-16-14 East St., Clark Rd., Van Buren Rd., Adams Rd.	2016	3,420	\$798,070
PW-17-02 Carter St., Cart Path Rd.	2017	3,251	\$592,483
PW-18-17 Main St., South St., Salem Road	2018	3,384	\$4,441,516
PW-18-18 North St. to Old Boston Rd.	2018	2,850	
PW-20-01 North St. to Victor Dr. & Old Boston Rd. to Marshall St.	2019	3,797	
PW-16-17 Woburn Street Area	2019	6,871	\$1,774,787
PW-20-08 South Tewksbury Upgrades – Phase I	2021	4,900	\$ ,941,544
PW-22-02 South Tewksbury Upgrades – Phase II	2021	5,950	\$2,609,738
PW-22-27 School Street	2022	1,505	\$399,468
PW-22-03 Pike St. and Astle St.	2022	2,860	\$1,002,534
PW-21-11 Whipple Rd. - Lowell Line to Chandler St.	2022	16,260	\$5,245,809
	<b>Total</b>	<b>59,497</b>	<b>\$12,973,880</b>

# Future Water Projects

Project Name	Year	Pipe Mat'l	Length (ft.)	Total Cost
Fiske Street	2024	AC	4,600	\$1,400,000
Hood Road, Cleghorn Road, Trull Brook Lane, Guile Road	2024	AC/Cast	6,300	\$1,900,000
Victor Drive	2024	Cast	1,650	\$500,000
Beech Street Neighborhood	2024	AC	5,050	\$1,550,000
South Tewksbury Phase III	2025	AC/WI	7,575	\$2,300,000
Shawsheen Street, Foster Road, Beech Street, Patten Road	2026	AC	3,100	\$1,000,000
Hill Street	2026	AC	2,000	\$600,000
Main Street Tie-Over	2027	AC	9,000	\$2,000,000
Pringle Street Neighborhood	2028	AC	6,900	\$2,100,000
William G Drive Neighborhood	2029	Cast	5,200	\$1,600,000
Cardigan Road Neighborhood	2030	Cast	5,050	\$1,550,000
South Tewksbury Phase IV	2031	AC	7,575	\$2,300,000
		<b>Total</b>	<b>64,000</b>	<b>\$18,800,000</b>

# Questions/Comments



# References

Camp Dresser & McKee, Inc. (2004). *Town of Tewksbury, Massachusetts Water Distribution System Master Plan*. Cambridge: Camp Dresserr & McKee, Inc.

CDM Smith. (2018). *Town of Tewksbury, Massachusetts 2004 Water Master Plan - UPDATES*. Boston: CMD Smith.

Tutella Engineering Associates, Inc. (1989). *Water Distribution Study and Network Analysis*. Wilmington: Tutella Engineering Associates, Inc.

Fisher, C. (2008, January/February). Chosing the Right Pipe. *Underground Infrastructure Management*, pp. 30-32.